



# Grid-Connected PV Systems Design and Installation

Revisions to the Grid-Connected PV Systems: Design and  
Installation Australian Edition Version 8.10 Publication

Following is the summary of changes to the information within Grid-Connected PV Systems Design and Installation Australian Edition Version 8.10, September 2021. Please note that the changes in this document are subject to alterations in newer editions. While all care has been taken to ensure this document is free from omission and error, no responsibility can be taken for the use of this information in the design or installation of any grid-connected PV system.

Copyright GSES; all rights reserved.

## Keywords

**Addition:** Adding an additional paragraph.

**Replacement:** To entirely replace something.

**Extension:** To add an additional sentence/s onto the end of a sentence or paragraph.

**Amendment:** To modify sections of a paragraph or sentence either by quote or by reviewing the referenced text.

**Removal:** To remove something altogether.

## Chapter 4

### 1. Chapter 4 Quiz

Replacement:

Question 4

Draw a rough I-V curve and power curve for a module with the following characteristics. Calculate and label the PMP and label all three axes.

- $V_{OC} = 45 \text{ V}$
- $V_{MP} = 35 \text{ V}$
- $I_{SC} = 8 \text{ A}$
- $I_{MP} = 7 \text{ A}$

## Chapter 7

### 2. Section 7.2.3

Replacement:




Figure 7.10: Example of an inverter efficiency curve (SMA Sunny Boy 5.0-1AV-41).  
(Source: SMA Solar Technology AG.)

### 3. Section 7.9.2 - Response to Decrease in Frequency

Amendment:

The inverter shall not reduce power output through the grid-interactive port in response to a decrease in frequency. In addition, if the inverter is not operating at full power due to another response mode, and the grid's frequency drops, the inverter must increase its output linearly to support the grid frequency. The power level present at the time that frequency falls below  $f_{LLCO}$  is used as a reference power level to calculate the required response to the decreasing frequency.

## Chapter 12

### 4. Chapter 12 Quiz: Question 3 Table

Amendment:

At 1,000 W/m <sup>2</sup> (STC)	
Maximum power	315W
Maximum power voltage ( $V_{MP}$ )	39.8V
Maximum power current ( $I_{MP}$ )	7.92 A
Open circuit voltage ( $V_{OC}$ )	49.2V
Short circuit current ( $I_{SC}$ )	8.50 A
Efficiency	14.3%
Other electrical characteristics	
Power tolerance	+5/-3%
Maximum system voltage	1,000V
Maximum reverse current	15 A
Series fuse rating	15 A
Temperature coefficient of $V_{OC}$	-0.36%/°C
Temperature coefficient of $I_{SC}$	0.061%/°C
Temperature coefficient of $P_{MAX}$	-0.46%/°C

### 5. Chapter 12 Quiz: Question 3

Amendment:

c. The inverter to be used has an MPPT minimum operating voltage of 150 V. The maximum expected cell temperature is 70°C and the voltage drop can be assumed to be 2% in the cables on the DC side. Use the temperature coefficient for  $P_{MAX}$  and calculate:

### 6. Chapter 12 Quiz: Question 3

Amendment:

c. ii The maximum power voltage temperature coefficient

## Chapter 14

### 7. Chapter 14 Quiz: Question 3

*Amendment:*

An array has four strings of nine modules and the following specifications:

- Module  $I_{SC} = 10.49 \text{ A}$
- Module  $V_{MP} = 34.1 \text{ V}$
- The length of the positive string cable is 8 m and the length of the negative string cable is 14 m from the furthest module to the disconnecter.
- Array cable length = 22 m
- The cables are XLPE 90°C copper, with a resistivity of  $0.0219 \Omega/\text{m}/\text{mm}^2$ . Assume the cable has the same specifications as in Table 14.2.

The cables should be sized to have a maximum 1.5% voltage drop on the string cables and a 1.5% voltage drop on the array cables.

- a. Calculate the minimum string cable CSA.
- b. Calculate the minimum array cable CSA.

### 8. Chapter 14 Quiz: Question 4

*Amendment:*

You are supplied with a reel of  $4 \text{ mm}^2$  cable to use as the array cable for a solar PV installation. The array has five strings of ten modules and the following specifications:

- Module  $I_{SC} = 10.05 \text{ A}$
  - Module  $V_{MP} = 33.24 \text{ V}$
  - String cable length = 20 m
  - Array cable length = 11 m
  - The cables are XLPE 90°C copper, with a resistivity of  $0.0219 \Omega/\text{m}/\text{mm}^2$ . Assume the cable has the same specifications as in Table 14.2.
- a. Calculate the % voltage drop on the array cable.
  - b. Calculate the maximum allowable % voltage drop on the string cables.
  - c. Calculate the minimum string cable CSA

### 9. Chapter 14 Quiz: Question 5

*Amendment:*

The distance between an inverter and the main switchboard is 26 m. What is the minimum cable CSA that will ensure the voltage drop will be less than 1%?

Assume the following:

- $I_{AC} = 12 \text{ A}$
- $V = \text{Single-phase } 230 \text{ V}_{RMS}$
- The cables are PVC 75°C copper, with a resistivity of  $0.0209 \Omega/\text{m}/\text{mm}^2$ .
- Power factor = 1

Assume the cable has the same specifications as in Table 14.2.

## Chapter 15

### 10. Section 15.1.7 - Inverter Efficiency

*Extension:*

Realistically the value of the inverter efficiency will usually be less than the peak efficiency specified on the inverter manufacturer's datasheet. For example, in Figure 7.10 the maximum efficiency of the Sunny Boy 5.0-1AV-41 is 97% however under most operating conditions, the efficiency will be between 95-97% as shown in the efficiency curve. This value may be more appropriate to use when calculating yield.

Average system losses due to the inverter are in the range of 2-6%, which is equivalent to an efficiency range of 94-98%.

## 11. Section 15.4 - Greenhouse Gas Savings

*Addition:*

The desire to help the environment and reduce the household's carbon footprint is also an influencing factor for the installation of a PV system. Each kWh of energy generated by the PV system is one less kWh that is required to be generated by the grid. Given that most of Australia's electricity is generated from coal, this represents an emissions reduction.

To estimate the amount of greenhouse gas savings by installing a PV system, the PV system's estimated electricity generation (kWh) is multiplied by an emission factor. This provides an estimation of the kilograms of Carbon Dioxide equivalent (CO<sub>2</sub>-e) that will be offset by the system.

Emissions factors vary depending on the state because each state uses technologies with different emissions intensities to produce their grid electricity. Victoria for example produces most of their power through brown coal power stations with high CO<sub>2</sub> emissions, whereas Tasmania produces most of their power through hydropower with low CO<sub>2</sub> emissions.

### **EXAMPLE**

A system installed in Sydney NSW generates an annual yield of 5295 kWh/year. Assume the GHG emission factor for NSW is 0.87 kg CO<sub>2</sub>-e/kWh. Estimate the annual greenhouse gas savings for the system.

$$\begin{aligned} & \text{Greenhouse Gas Savings (kg CO}_2\text{-e /year)} \\ &= \text{Electricity Production (kWh/year)} \times \text{emission factor (kg CO}_2\text{-e/kWh)} \\ &= 5295 \text{ kWh/year} \times 0.87 \text{ kg CO}_2\text{-e/kWh} \\ &= 4606.65 \text{ kg CO}_2\text{-e/year} \end{aligned}$$

Therefore the system will save 4606.65 kg CO<sub>2</sub>-e each year. Note that this is independent of whether the solar generation is consumed within the household or not.

## Chapter 17

### 12. Introduction

*Addition:*

#### **IMPORTANT**

The Australian Energy Market Operator operates the distributed energy resource (DER) register. This means that installers need to provide additional information to network service providers (NSPs) or directly to AEMO (depending on the NSP) about the PV systems they are installing. Installers must be across these requirements. Check with your local NSP and refer to the AEMO website (<https://www.aemo.com.au/energy-systems/electricity/der-register>) for more information.

### 13. Commissioning & Verification Checklist

*Amendment:*

A verification checklist may be used as a quality assurance tool to confirm that all qualitative design and installation criteria have been met. **A sample system commissioning checklist is included in Section 17.2.8 in conjunction with a sample testing and commissioning sheet.**

### 14. Commissioning & Verification Checklist

*Removal:*

Installer name:	
Installer accreditation number (if applicable):	
Installer signature:	
Commissioning date:	
Installation address:	
Client name:	
Client contact details:	
PV module manufacturer:	PV module model number:
PV module installation meets relevant building codes: YES <input type="checkbox"/> NO <input type="checkbox"/>	
All PV modules connected to the same MPPT are of the same make and model or have similar rated electrical characteristics: YES <input type="checkbox"/> NO <input type="checkbox"/>	
All PV modules connected to the same string have the same angle of tilt and azimuth: YES <input type="checkbox"/> NO <input type="checkbox"/>	
Number of modules in series:	Number of strings in parallel:
String 1:	Sub-array 1:
String 2:	Sub-array 2:
String 3:	Sub-array 3:
String n: (add more as required)	Sub-array n: (add more as required)
Array mounting system manufacturer:	
Array mounting system model:	
Array mounting system certified for installation site parameters: YES <input type="checkbox"/> NO <input type="checkbox"/>	
Array mounting system does not use or contact any galvanically dissimilar metals: YES <input type="checkbox"/> NO <input type="checkbox"/>	
All penetrations and fixings are suitably sealed and weatherproofed: YES <input type="checkbox"/> NO <input type="checkbox"/>	
PV array voltage complies with site regulations: YES <input type="checkbox"/> NO <input type="checkbox"/>	
PV system wiring is suitably protected from mechanical action: YES <input type="checkbox"/> NO <input type="checkbox"/>	
PV array uses single-core double-insulated cabling compliant to relevant standards: YES <input type="checkbox"/> NO <input type="checkbox"/>	
Overcurrent protection is provided where required: YES <input type="checkbox"/> NO <input type="checkbox"/> NOT REQUIRED <input type="checkbox"/>	

<p>All DC components are rated correctly for DC usage and have voltage ratings greater than or equal to the PV array maximum voltage:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p> <p>All AC components are rated correctly for AC usage.  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>All components are suitable for their environment and have the appropriate IP and UV ratings:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Disconnection devices and protection devices (where installed) are readily available in the case of maintenance or emergency:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Disconnecting devices comply with frequency-of-use requirements and are rated for the temperature-adjusted operational circuit current:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Disconnectors are rated to switch full-load currents (where required) and are not polarity-sensitive (in the case of DC circuit breakers):  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>PV array disconnectors interrupt all live conductors:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>PV conductor current-carrying capacity is equal to or greater than the potential system fault current or the overcurrent protection (where installed):  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>PV cabling, where exposed to the elements, is UV-resistant or installed in UV-resistant enclosures:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>A method of securing cabling has been used that will last the lifetime of the system:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>DC cabling within buildings is enclosed in heavy-duty-rated protection:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/> <b>NOT REQUIRED</b> <input type="checkbox"/></p>
<p>Combiner boxes are installed according to manufacturer recommendations:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Combiner boxes are suitably protected from the environment using appropriate bottom-entry cable glands:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Double insulation between all conductors is maintained throughout the system:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>PV plugs, sockets and connectors comply with relevant standards, are rated for the installation environment and connect only with the same make and model:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Blocking and bypass diodes, where installed external to the PV module are suitably protected and grade according to relevant standards and system parameters:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/></p>
<p>Overcurrent protection (where required) is installed at the end of the conductor that is most electrically remote from the PV modules:  <b>YES</b> <input type="checkbox"/> <b>NO</b> <input type="checkbox"/> <b>NOT REQUIRED</b> <input type="checkbox"/></p>

A DC disconnecter is located adjacent to the inverter if the array is not in line of sight from the inverter: YES <input type="checkbox"/> NO <input type="checkbox"/>
Where multiple DC disconnection devices are installed, they are ganged together or grouped and labelled such that it is clear that all must be operated to isolate the system: YES <input type="checkbox"/> NO <input type="checkbox"/> NOT REQUIRED <input type="checkbox"/>
All exposed metal module frames and mounting equipment are earthed and equipotentially bonded in accordance with the relevant standards: YES <input type="checkbox"/> NO <input type="checkbox"/>
Equipment used for PV module and mounting frame earth connections is fit for purpose: YES <input type="checkbox"/> NO <input type="checkbox"/>
Earthing has been arranged so that the removal of a single module earth connection will not disrupt the continuity of the bonding connections for the rest of the array: YES <input type="checkbox"/> NO <input type="checkbox"/>
Earthing conductor type and size comply with the relevant standards: YES <input type="checkbox"/> NO <input type="checkbox"/>
PV array functional earthing is done close to or within the inverter and is done according to the relevant standards: YES <input type="checkbox"/> NO <input type="checkbox"/> NOT REQUIRED <input type="checkbox"/>
The inverter complies with the relevant country standards: YES <input type="checkbox"/> NO <input type="checkbox"/>
The inverter installation complies with the manufacturer's instructions, the distribution network service provider's rules and regulations and relevant legislation: YES <input type="checkbox"/> NO <input type="checkbox"/>
Inverters connected to LV PV arrays have an internal or external earth fault alarm system: YES <input type="checkbox"/> NO <input type="checkbox"/>
Inverters connected to arrays with direct functional earthing have an earth fault interrupter, which will shut the PV system down and provide a fault alarm when an earth fault occurs: YES <input type="checkbox"/> NO <input type="checkbox"/> NOT REQUIRED <input type="checkbox"/>
Signage and labelling conforms to the relevant standards and guidelines: YES <input type="checkbox"/> NO <input type="checkbox"/>

## 15. Section 17.2.8 - Test Records

*Addition:*

### Example test records

The following pages contain a sample commissioning checklist as well as a sample testing and commissioning sheet which could be used as part of the system commissioning.

Clean Energy Council Limited (ABN 84 127 102 443) owns the copyright in this material and grants use of this material to GSES for the purpose of inclusion in its training manual (May 2021). Disclaimer: This template checklist has been prepared by the CEC for use by accredited installers. The CEC is not responsible for and does not guarantee or accept any liability whatsoever for the accuracy or completeness of the information contained in the checklist.

# GRID-CONNECTED SOLAR PV POWER SYSTEM COMMISSIONING CHECKLIST

VERSION 1.1, NOVEMBER 2020

System address	
Systems owner's name	
System owner's email address	
System owner's phone number	
My Jobs reference number (optional)	
Date of installation	
<b>Please tick and/or insert a value for each relevant field to confirm compliance for this job.</b>	
<b>Mark any unrequired fields as NA (not applicable).</b>	
Building type	<input type="checkbox"/> Domestic <input type="checkbox"/> Non-domestic
National meter identifier (NMI)	
Meter number	
Number of phases (supply)	
Distribution network service provider (DNSP)	
Energy retailer at the time of commissioning	
Network preapproval reference	
Export limiting requirements	
<b>PV MODULE (SOLAR PANEL) CHECKLIST</b>	
Panel manufacturer	
Panel model	
Panel DC connector manufacturer	
Panel DC connector type/model <i>e.g. MC-4 or MC-4EVO2</i>	
STRING 1: Number of panels / orientation (azimuth/tilt) / MPPT # <i>e.g. 12 / 270° / 30° / MPPT 1</i>	/ / /
STRING 2: Number of panels / orientation (azimuth/tilt) / MPPT #	/ / /
STRING 3: Number of panels / orientation (azimuth/tilt) / MPPT #	/ / /
STRING 4: Number of panels / orientation (azimuth/tilt) / MPPT #	/ / /
STRING 5: Number of panels / orientation (azimuth/tilt) / MPPT #	/ / /
STRING 6: Number of panels / orientation (azimuth/tilt) / MPPT #	/ / /
String fuse current and voltage rating if installed <i>e.g. 15A / 1000V</i>	/
PV array short circuit current – calculated as the sum of all the array currents at STC	A
PV array maximum voltage – calculated for lowest operating temperature	V
<b>DC LOAD BREAKING DISCONNECTOR (DC ISOLATOR) CHECKLIST</b>	
<b>DC isolators</b>	
DC isolator manufacturer/s	
DC isolator model/s	
Number of DC isolators	
<b>All DC isolators are correctly rated and configured for the PV arrays they isolate</b>	<input type="checkbox"/>



Disclaimer: This template checklist has been prepared by the CEC for use by accredited installers. The CEC is not responsible for and does not guarantee or accept any liability whatsoever for the accuracy or completeness of the information contained in the checklist.

<b>Inverter integrated DC isolators</b>	
The inverter has an integrated DC isolator	<input type="checkbox"/>
The inverter integrated DC isolator meets all the requirements in the Australian standards	<input type="checkbox"/>
A manufacturer's specification (spec) sheet and declaration has been provided and included with system documentation	<input type="checkbox"/> Spec sheet <input type="checkbox"/> Declaration
Does the local state or territory regulator require a physically separate adjacent DC isolator to be installed at the inverter (PCE)?	
<b>Installation and testing of DC isolators</b>	
DC isolators enclosures IP maintained <i>e.g. orientation approved, pips installed if supplied</i>	<input type="checkbox"/>
DC isolators installed to all relevant standards, guidelines, and manufacturer's instructions.	<input type="checkbox"/>
<b>All DC isolators have been tested (turned off) under load</b>	<input type="checkbox"/>
<b>CONDUIT AND CABLING CHECKLIST</b>	
Conduit compliantly installed and adequately supported <i>e.g. glued, secured and labelled</i>	<input type="checkbox"/>
Roof penetrations for cabling system adequately sealed <i>e.g. appropriate collard flashing for roof material</i>	<input type="checkbox"/>
Cable is mechanically protected and supported as per AS/NZS 3000 and AS/NZS 5033	<input type="checkbox"/>
DC cable volt drop (Vd) is less than 3%	<input type="checkbox"/> Voltage drop                      %
<b>INVERTER (PCE) CHECKLIST</b>	
Inverter manufacturer	
Inverter model	
Number of inverters	
Number of maximum power point trackers (MPPT)	
Maximum inverter DC input power	W
Maximum inverter DC input current per MPPT	A
Maximum inverter DC input short circuit current per MPPT	A
The inverter is installed to all relevant standards, guidelines, and manufacturer's instructions	<input type="checkbox"/>
The AC isolator (if required) is mounted adjacent to the inverter and is correctly rated and lockable	<input type="checkbox"/>
The AC circuit breaker is mounted in the switchboard and is correctly rated and lockable	<input type="checkbox"/>
The AC cable voltage rise from inverter terminals to the point of supply is less than 2%	<input type="checkbox"/> Voltage rise                      %
AC voltage at inverter terminals under load and no-load	V /                      V
<b>MOUNTING STRUCTURE (MOUNTING SYSTEM) CHECKLIST</b>	
Mounting system manufacturer	
Mounting system model	
The mounting system is installed to all relevant standards, guidelines, and manufacturer's instructions	<input type="checkbox"/>



Disclaimer: This template checklist has been prepared by the CEC for use by accredited installers. The CEC is not responsible for and does not guarantee or accept any liability whatsoever for the accuracy or completeness of the information contained in the checklist.

The roof penetrations for the mounting system are adequately sealed <i>e.g. tiles maintain their original ingress protection</i>	<input type="checkbox"/>
The mounting system manufacturer's exclusion zones are adhered to and meet the minimum requirement of AS/NZS 1170.2	<input type="checkbox"/>
The array frame is certified to AS/NZS 1170.2	<input type="checkbox"/>
Galvanically dissimilar metals are <b>not</b> in contact with each other <i>e.g. separated by nylon or rubber spacers</i>	<input type="checkbox"/>
The panels are installed to the panel manufacturer's instructions	<input type="checkbox"/>
The panels are installed within the manufacturer's clamping zones	<input type="checkbox"/>
All bolts and terminations are correctly torqued	<input type="checkbox"/>
Mounting system and panels are correctly earthed	<input type="checkbox"/>
Earth connections are UV and mechanically protected <i>e.g. gal sprayed</i>	<input type="checkbox"/>
Earth fault alarm type <i>e.g. visual, audible, electronic, etc.</i>	
<b>OTHER</b>	
System is labelled as per requirements in AS/NZS 3000, AS/NZS 5033, AS/NZS 4777.1 and CEC guidelines	<input type="checkbox"/> AS/NZS 3000 <input type="checkbox"/> AS/NZS 5033 <input type="checkbox"/> AS/NZS 4777.1 <input type="checkbox"/> CEC Guidelines
LV wiring system installed by a licensed electrical worker	<input type="checkbox"/>
LV wiring system tested and certified by a licensed electrical worker	<input type="checkbox"/>
System is compliant as per AS/NZS 5033 <i>Section 5 - Marking &amp; Documentation, and Appendix A</i>	<input type="checkbox"/>
Distributed energy resource (DER) documented as per NSP requirements	<input type="checkbox"/>
<b>Inverter settings</b>	
<b>Inverter is installed as per network service provider (NSP) Connection Agreement</b>	<input type="checkbox"/>
Country code settings are set to Australia	<input type="checkbox"/>
Volt Var - setting <i>e.g. 250V / 40%</i>	V / %
Volt Var - setting – V2	V / %
Volt Var - setting – V3	V / %
Volt Var - setting – V4	V / %
Volt Watt - setting <i>e.g. 250V / 30%</i>	V / %
Volt Watt – setting – V2	V / %
Volt Watt – setting – V3	V / %
Volt Watt – setting – V4	V / %
Export limit - setting	W
Inverter shuts down within 2 seconds of isolation	<input type="checkbox"/>
Inverter takes at least 60 seconds to start after re-connection to supply	<input type="checkbox"/>
Inverter then takes 6 minutes to ramp up to 100%	<input type="checkbox"/>



Disclaimer: This template checklist has been prepared by the CEC for use by accredited installers. The CEC is not responsible for and does not guarantee or accept any liability whatsoever for the accuracy or completeness of the information contained in the checklist.

**TESTING AND COMMISSIONING SHEET**

Commissioning Information Details Using the panel nameplate information	Calculated Information Details Refer to AS/NZS 5033:2014 Cl 4.2 a, b, c and Cl 5.4.1		Commissioning Test Details Refer to AS/NZS 5033 Appendix D for correct testing procedures.					Commissioning Information Details Measured at, or obtained from PCE				
	Voc (V)	Isc (A)	PV Array Maximum Voltage PVAMV (V)	Continuity of strings and correct polarity (Y or N)	Earth continuity (Ω)	Insulation resistance (M Ω) +ve to E / -ve to E	Non-Operational condition at time of testing (No load condition)		Operational condition at time of commissioning. (Under Load condition)			
						Open circuit voltage -Voc (V)	*Short circuit current - Isc (A)	*Irrad (W/M <sup>2</sup> )	Operational Voltage (V)	Operational Current (A)	Power (W)	*Irrad (W/M <sup>2</sup> )
Array												
String 1												
String 2												
String 3												
String 4												
String 5												
String 6												
MPPT 1												
MPPT 2												
MPPT 3												

Greyed out cells may not be required depending on specific system design but can assist an installer in confirming correct system operation.  
**\*Note: non-mandatory**



Disclaimer: This template checklist has been prepared by the CEC for use by accredited installers. The CEC is not responsible for and does not guarantee or accept any liability whatsoever for the accuracy or completeness of the information contained in the checklist.

**DECLARATION OF RESPONSIBLE PERSONS**

I hereby sign and verify that this system has been designed, installed and commissioned to all relevant Australian standards, state and territory regulations, and CEC guidelines.

CEC-accredited designer's name	
CEC accreditation no.	
Date:	Sign:
CEC-accredited installer's name	
CEC accreditation no.	
Date:	Sign:
Licensed electrician's name	
Licensed electrician no.	
Date:	Sign:

**SYSTEM OWNER'S DECLARATION**

I confirm that I have received an operating manual and have been instructed on the safe operation of the system.	<input type="checkbox"/>
I confirm that the CEC-accredited installer named above: <ul style="list-style-type: none"> <li>a. Is the installer that physically undertook the installation, or;</li> <li>b. Supervised the installation by physically attending the site at three stages of the installation, at job set-up (beginning), mid-installation check-up (during), and testing and commissioning (end).</li> </ul>	a. <input type="checkbox"/> or b. <input type="checkbox"/>
System owner's name:	
Date:	Sign::



Disclaimer: This template checklist has been prepared by the CEC for use by accredited installers. The CEC is not responsible for and does not guarantee or accept any liability whatsoever for the accuracy or completeness of the information contained in the checklist.

## Appendix 5: Quiz Answers

### 16. Chapter 12: Question 3 - (c) ii

Amendment:

$$\begin{aligned} \gamma_{VMP} \left(\frac{\text{V}}{\text{C}}\right) &= \frac{\gamma_{PMP} \left(\frac{\%}{\text{C}}\right)}{100} \times V_{MP} \\ &= \frac{-0.46}{100} \times 39.8 \text{ V} \\ &= -0.183 \left(\frac{\text{V}}{\text{C}}\right) \end{aligned}$$

### 17. Chapter 12: Question 3 - (c) iii

Amendment:

$$\begin{aligned} V_{MP \text{ at } 70^{\circ}\text{C}} &= [V_{MP \text{ at } STC} + (\gamma_{VMP} \times (T_{X^{\circ}\text{C}} - T_{STC}))] \\ &= [39.8 \text{ V} + (-0.183 \text{ V/}^{\circ}\text{C} \times 45^{\circ}\text{C})] \\ &= 31.57 \text{ V} \end{aligned}$$

### 18. Chapter 12: Question 3 - (d) iii

Replacement:

$$\begin{aligned} V_{OC \text{ at } 0^{\circ}\text{C}} &= V_{OC \text{ at } STC} + (\gamma_{VOC} \times \text{cell temperature difference}) \\ &= 49.2 \text{ V} + (-0.177 \text{ V/}^{\circ}\text{C} \times -25^{\circ}\text{C}) \\ &= 53.63 \text{ V} \end{aligned}$$

### 19. Chapter 12: Question 3 - (d) iv

Removal:

$$\begin{aligned} V_{MP \text{ at } 0^{\circ}\text{C}} &= V_{MP \text{ at } STC} - (\gamma_{VOC} \times \text{cell temperature difference}) \\ &= 39.8 \text{ V} - (0.177 \text{ V/}^{\circ}\text{C} \times -25^{\circ}\text{C}) \\ &= 44.23 \text{ V} \end{aligned}$$

### 20. Chapter 12: Question 3 - (d) v

Removal:

$$\begin{aligned} \text{Maximum number of modules } (V_{MP}) &= \frac{\text{maximum MPPT voltage} \times \text{safety margin}}{V_{MP \text{ at } 0^{\circ}\text{C}}} \\ &= \frac{500 \times 0.95}{44.23} \\ &= 10.74 \text{ modules} \end{aligned}$$

## 21. Chapter 14: Question 3

Replacement:

a. String cable:

Using the Simple Resistivity Method:

$$\begin{aligned}A_{\text{CABLE}} &= \frac{(L_{+\text{CABLE}} + L_{-\text{CABLE}}) \times I \times \rho}{\text{Loss} \times V_{\text{MAX}}} \\&= \frac{(8 \text{ m} + 14 \text{ m}) \times 10.49 \text{ A} \times 0.0219 \text{ } \Omega/\text{m}/\text{mm}^2}{0.015 \times (9 \times 34.1) \text{ V}} \\&= 1.098 \text{ mm}^2\end{aligned}$$

Using Table 14.2 and the  $V_c$  AS/NZS 3008.1.1:2017 Method:

$$\begin{aligned}\text{Maximum } V_c &= \frac{1,000 \times \text{Loss} \times V_{\text{MAX}}}{L \times I} \\&= \frac{1,000 \times 0.015 \times (9 \times 34.1) \text{ V}}{14 \text{ m} \times 10.49 \text{ A}} \\&= 31.35 \text{ mV/Am (DC)}\end{aligned}$$

Converting to three-phase:

$$\frac{31.35 \text{ mV/Am}}{1.155} = 27.14 \text{ mV/Am (three-phase AC)}$$

Assuming the selected cable may operate up to its rated insulation temperature of 90°C, the minimum conductor CSA that meets the calculated  $V_c$  requirement is a 2.5 mm<sup>2</sup> cable.

b. Array cable:

Using the Simple Resistivity Method:

$$\begin{aligned}A_{\text{CABLE}} &= \frac{2 \times L \times I \times \rho}{\text{Loss} \times V_{\text{MAX}}} \\&= \frac{2 \times 22 \text{ m} \times (4 \times 10.49) \text{ A} \times 0.0219 \text{ } \Omega/\text{m}/\text{mm}^2}{0.015 \times (9 \times 34.1) \text{ V}} \\&= 8.78 \text{ mm}^2\end{aligned}$$

Using Table 14.2 and the  $V_c$  AS/NZS 3008.1.1:2017 Method:

$$\begin{aligned}\text{Maximum } V_c &= \frac{1,000 \times \text{Loss} \times V_{\text{MAX}}}{L \times I} \\&= \frac{1,000 \times 0.015 \times (9 \times 34.1) \text{ V}}{22 \text{ m} \times (4 \times 10.49 \text{ A})} \\&= 4.99 \text{ mV/Am (DC)}\end{aligned}$$

Converting to three-phase:

$$\frac{4.99 \text{ mV/Am}}{1.155} = 4.32 \text{ mV/Am (three-phase AC)}$$

Assuming the selected cable may operate up to its rated insulation temperature of 90°C, the minimum conductor CSA that meets the calculated  $V_c$  requirement is a 10 mm<sup>2</sup> cable.

## 22. Chapter 14: Question 4

Replacement:

a. Array cable:

Using the Simple Resistivity Method:

$$\begin{aligned}
 V_d &= \frac{2 \times L \times I \times \rho}{A_{\text{CABLE}}} \\
 &= \frac{2 \times 11 \text{ m} \times (5 \times 10.05) \text{ A} \times 0.0219 \text{ } \Omega/\text{m}/\text{mm}^2}{4 \text{ mm}^2} \\
 &= 6.05 \text{ mm}^2 \\
 \text{Loss} &= \frac{V_d}{V_{\text{MAX}}} \\
 &= \frac{6.05 \text{ V}}{(10 \times 33.24) \text{ V}} \\
 &= 0.018 \\
 &= 1.8 \%
 \end{aligned}$$

Using the  $V_c$  AS/NZS 3008.1.1:2017 Method:

$$\begin{aligned}
 V_d &= \frac{L \times I \times V_c}{1,000} \\
 &= \frac{11 \text{ m} \times (5 \times 10.05) \text{ A} \times (10.9 \times 1.155) \text{ mV/Am}}{1,000} \\
 &= 6.96 \text{ V} \\
 \text{Loss} &= \frac{V_d}{V_{\text{MAX}}} \\
 &= \frac{6.96 \text{ V}}{(10 \times 33.24) \text{ V}} \\
 &= 0.022 \\
 &= 2.2 \%
 \end{aligned}$$

b. String cable:

Using the Simple Resistivity Method result:

$$\begin{aligned}
 V_{\text{DROP ALLOWABLE STRING CABLE}} &= V_{\text{DROP MAX}} - V_{\text{DROP ARRAY CABLE}} \\
 &= 3.0 \% - 1.8 \% \\
 &= 1.2 \%
 \end{aligned}$$

Using the  $V_c$  AS/NZS 3008.1.1:2017 Method result:

$$\begin{aligned}
 V_{\text{DROP ALLOWABLE STRING CABLE}} &= V_{\text{DROP MAX}} - V_{\text{DROP ARRAY CABLE}} \\
 &= 3.0 \% - 2.2 \% \\
 &= 0.8 \%
 \end{aligned}$$

c. String cable CSA:

Using the Simple Resistivity Method result:

$$\begin{aligned}
 A_{\text{CABLE}} &= \frac{2 \times L \times I \times \rho}{\text{Loss} \times V_{\text{MAX}}} \\
 &= \frac{2 \times 20 \text{ m} \times 10.05 \text{ A} \times 0.0219 \text{ } \Omega/\text{m}/\text{mm}^2}{0.012 \times (10 \times 33.24) \text{ V}} \\
 &= 2.21 \text{ mm}^2
 \end{aligned}$$

Using [Table 14.2](#) and the  $V_c$  AS/NZS 3008.1.1:2017 Method:

$$\begin{aligned}
 \text{Maximum } V_c &= \frac{1,000 \times \text{Loss} \times V_{\text{MAX}}}{L \times I} \\
 &= \frac{1,000 \times 0.008 \times (10 \times 33.24) \text{ V}}{20 \text{ m} \times 10.05 \text{ A}} \\
 &= 13.23 \text{ mV/Am (DC)}
 \end{aligned}$$

Converting to three-phase:

$$\frac{13.23 \text{ mV/Am}}{1.155} = 11.45 \text{ mV/Am (three-phase AC)}$$

Assuming the selected cable may operate up to its rated insulation temperature of 90°C, the minimum conductor CSA that meets the calculated  $V_c$  requirement is a 4 mm<sup>2</sup> cable

### 23. Chapter 14: Question 5

Replacement:

AC cable:

Using the Simple Resistivity Method, the minimum cable size for the AC cables is calculated as follows:

$$\begin{aligned} A_{\text{CABLE}} &= \frac{2 \times L \times I \times \rho \times \cos\Phi}{\text{Loss} \times V_{\text{MAX}}} \\ &= \frac{2 \times 26 \text{ m} \times 12 \text{ A} \times 0.0209 \text{ } \Omega/\text{m}/\text{mm}^2}{0.01 \times 230 \text{ V}} \\ &= 5.67 \text{ mm}^2 \end{aligned}$$

Using Table 14.2 and the  $V_c$  AS/NZS 3008.1.1:2017 Method:

$$\begin{aligned} \text{Maximum } V_c &= \frac{1,000 \times \text{Loss} \times V_{\text{AC}}}{L \times I} \\ &= \frac{1,000 \times 0.01 \times 230 \text{ V}}{26 \text{ m} \times 12 \text{ A}} \\ &= 7.37 \text{ mV/Am (DC)} \end{aligned}$$

Converting to three-phase:

$$\frac{7.37 \text{ mV/Am}}{1.155} = 6.38 \text{ mV/Am (three-phase AC)}$$

Assuming the selected cable may operate up to its rated insulation temperature of 75°C, the minimum conductor CSA that meets the calculated  $V_c$  requirement is a 10 mm<sup>2</sup> cable.

### 24. Chapter 15: Question 4 - (b)

Amendment:

$$\text{Energy yield} = \text{Array rated power} \times \text{Irradiation} \times \text{System efficiency}$$

$$\text{Array rated power} = \frac{\text{Energy yield}}{\text{Irradiation} \times \text{System efficiency}}$$

$$\text{Array rated power} = \frac{13,000 \text{ kWh}}{1,352.33 \text{ kWh/m}^2/\text{year} \times 0.789} = 12.18 \text{ kW}$$

$$\text{Number of modules} = \frac{12.18 \text{ kW}}{0.24 \text{ kW}} = 50.75 = 51 \text{ modules}$$